


34-19-33W *680*

ATLANTIC REFG. CO.
 Rosine Smith No. 1.

SEC.34 T.19 R.33W
 CNE NE

Total Depth. 4800'
 Comm. 7-12-41 Comp. 8-7-41
 Shot or Treated.
 Contractor.
 Issued. 8-30-41 Rotary O-4800

County. Scott



CASING:
 10³/₄" 266' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface	25	Hole was filled with cement
sand & shale	165	from 4800 to 4700. Plgd
shale & shell	260	w/mud from 4700 to 276 w/
shale	295	cement and mud to 30'.
shale & shells	625	From 30' to 8' w/cement
shale & strks sand	770	and then mud to top of
sand sft	850	surface.
shale & shells	1170	
shale & sand	1445	
shale & shells	1525	
salt, lime, shells, &		
strks shale	1720	
shale	1890	
lime brkn	1970	
shale & red rock	2175	
anhydrite	2195	
shale & sand	2211	
shale, shells, strks sand	2370	
shale & shells	2600	
shale	2640	
shale & shells	2762	
shale	2815	
lime brkn & shale	2991	
shale & lime	3052	
lime & strks shale	3127	
lime & shale	3168	
lime hrd	3218	
lime & shale	3271	
lime	3378	
shale & lime	3424	
lime brkn	3610	
lime	3685	
lime brkn	3842	
lime	4078	
lime hd gy	4105	
lime	4333	
lime & strks shale	4349	
lime	4575	
shale sdy	4585	
brkn shale & strks sand	4596	
shale & brkn sdy shale	4602	
shale & sdy lime	4620	
lime sdy	4622	
sdylime & sand	4631	
lime	4640	
lime sdy	4685	
lime	4695	
lime sdy	4706	
chert, sdy lime	4712	
lime	4783	
chert	4787	
lime & chert	4791	
lime	4800	
Total Depth.		

Top Mississippi 4609