

State Geological Survey  
WICHITA BRAND

15-171-20151

KANSAS DRILLERS LOG

S. 36 T. 19 R. 33 E. W  
Loc. C NW NW  
County Scott

API No. 15 — 171 — 20,151  
County Number

Operator  
The Maurice L. Brown Company

Address  
200 Sutton Place, Wichita, Kansas 67202


Well No. 1 Lease Name Patton "B"

Footage Location  
660 feet from (N) line 660 feet from (W) line

Principal Contractor Slawson Drlg. Co. Geologist Raymond E. Palmer

Spud Date 10/4/77 Total Depth 4997' P.B.T.D. 4168

Date Completed 1/13/78 Oil Purchaser Permian



Locate well correctly  
Elev.: Gr. 2950  
DF KB 2955

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	366'	Howco Lite Class "H"	150	3% CC, 1/4# Flocele
Production	7 7/8"	5 1/2"	15 1/2#	4996'	65/35 Pozmix	300	3% CC, 1/4# Flocele 10% salt, 10# Gilsonite, 3/4% CFR <sub>2</sub> , 1/2# tuffibers/sx

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			20	Jumbo Jets	4074-84'
TUBING RECORD			20	Bullets	"
Size	Setting depth	Packer set at	4	Jumbo Jets	4073-76'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
DOC Squeeze - 85 sxs.	4074-84'

INITIAL PRODUCTION

Date of first production 1/13/78	Producing method (flowing, pumping, gas lift, etc.) Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil 25 bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s) 4073-76'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

