


30-19-4W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,                      Wichita, Kansas

Company-SKELLY OIL COMPANY  
Farm- Conway                      No. 5

SEC. 30    T. 19    R. 4W  
NE SW SW NE  
447'7" fr SL  
651' fr WL NE  $\frac{1}{4}$   
County McPherson  
KANSAS

Total Depth. 660  
Comm. 8-31-53                      Comp. 9-3-53  
Shot or Treated.  
Contractor. Claude Wentworth Drlg. Co.  
Issued. 12-5-53



CASING:  
8 5/8" 560' com. w/350 sx  
7 " 567'

Elevation. 1548' DF

Production. LPG Storage

Figures indicate Bottom of Formations.

|                      |     |
|----------------------|-----|
| surface dirt, clay & |     |
| sand                 | 30  |
| clay & shalo         | 60  |
| shalo & shells       | 415 |
| salt                 | 660 |
| Total Depth          |     |

TOPS:  
Wellington Salt 428  
Base Major Shalo Broak 556

Ran ~~Indo~~-Wells Gamma Ray Neutron Survey

560-565' Tested 8 5/8" OD csg.  
    to 150# for 2 hrs.,  
    tested OK.  
565-660' Tested to 200# for 1 hr.,  
    tested OK.