


3-19-40W
C NE SW

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579



WELL LOG -----
Located: 1980' FWL, 1980 FSL, SW/4, Sec. 3-19S-40W,
Creeley County, Kansas

A. G. FECHT #1

OWNER: Pierce and Dehlinger
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 6, 1971
COMPLETED: December 22, 1971

TOTAL DEPTH: 5460'

LOC	DESCRIPTION
0 - 440	Sand
440 - 800	Shale
800 - 1425	Sand and Shale
1425 - 1610	Shale and Lime
1610 - 2371	Shald and Sand
2371 - 2889	Shale and Lime
2889 - 2914	Lime
2914 - 2940	Sand and Shale
2940 - 3050	Lime, Sand - shale
3050 - 4120	Lime and Shale
4120 - 4215	Lime
4215 - 4435	Lime and Shale
4435 - 4528	Lime
4528 - 4695	Lime and Shale
4695 - 4785	Lime
4785 - 4950	Lime and Shale
4950 - 5094	Sand and Shale
5094 - 5460	Lime

CASING RECORD

Ran 12 joints 8 5/8" 24# (388.33')
Set at 405' K.B. Cemented with 300
sacks cement 3% c.c. Plug down at
11:15 AM, 12-7-71.

LOG TOPS

SC	2502
L FT R	2925
CO GR	3078
NEVA	3216
VIRGIL	3486
TOP	3724
HEEB	3982
LANS	4002
MARM	4476
CHER	4642
ATOKA	4788
MRW	4948
STE GEN	5118
ST LOUIS	5178
SPERG	5260
MISS OS	5424

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1972
CONSERVATION DIVISION
Wichita, Kansas



Plugged.