


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

18-19-40W

Company- GENERAL CRUDE OIL CO. & VAN-GRISSE OIL CO. SEC. 18 T. 19 R. 40W
Farm- W. Edman No. 1 C SW SW

Total Depth. 4046'
Comm. 9-12-57 Comp. 9-27-57
Shot or Treated.
Contractor.
Issued. 11-23-57

County Greeley
KANSAS



CASING:
10 3/4" 411'
5 1/2" 3010'

Elevation. 3632' RE

Production, 160,000 CFG

Figures indicate Bottom of Formations.

surface sands & clays	200
shale	595
shale & sand	944
sand (Dakota)	1010
shale & lime	1120
sand (Cheyenne)	1164
shale & lime	1685
red bed & shale	2724
red bed, shale & lime strks	2896
lime & red bed	2979
sandy shale & red bed	3264
lime & shale	4042
lime	4046
Total Depth	

TOPS: SCOUT

Chase	2765
Doyle	2842
Towanda	2877
Council Grove	3035
Admire	3353
Wabaunsee	3497
Topeka	3826
Heebner	4026

Core #1 2856-2896, recovered 40'.
Core #2 2897-2930, recovered 33'.
Core #3 2930-2979, recovered 49'.
Core #4 3975-4006, recovered 31'.

DRILL STEM TESTS:

#1 2872-2930, misrun.

#2 2872-2930, tool opened 1 hr & 30 mins.
gas to surface in 27 mins. (flowed at
rate of 26.8 MCF per day). Recovered
90' of slightly gas cut mud, 210' of
very heavily gas cut mud and 90' of
muddy salt water. FP 90-170, SIP 500-
525/30 mins., HMP 1520-1500.

#3 2930-2979, tool op. 1 hr & 30 mins.
no gas to surface. Recovered 165'
of very slightly gas cut rathole mud.
FP 70-100, SIP 180/20 mins. & 235/30 mins.
HMP 1470-1435.

#4 3772-3808, tool op. 1 hr. no gas to
surface. Recovered 320' of muddy, sulfur wtr.
slightly gas cut, strong sulfur odor.
FP 25-190, SIP 970/15 mins. & 880/30 mins.
HMP 1900-1850.

Perforation Record: 2906-2915 (Winfield)
with 6 shots per foot.

Treated the well with 1000 gallons of