

KANSAS GEOLOGICAL SOCIETY,
508 East Murdock
Wichita, Kansas

DEC 5 1970

Co-BROOKS HALL CORPORATION

THOMPSON WELL NO. 1
Greeley County, Kansas

28-1940W
CNE/4

Dry/min
Elev. 3606' KB

COMMENCED OPERATIONS: 8-17-68
COMPLETED OPERATIONS: 9-1-68

DRILLERS LOG

8-17-68	<u>Log Tags</u>	0 - 290	Sand.
8-18-68	SC	290 - 980	Blue Shale, Shale & Sand.
8-19-68	Chase 2477	980 - 1725	Shale, Gypsum & Anhydrite.
	Cumil H. 2949	1725 - 2176	Sand.
	Walash 3326	2176 - 2487	Shale & Anhydrite.
8-20-68	Shaw. 3616	2487 - 3183	Shale & Anhydrite.
8-21-68	Lansing 3704	3183 - 3439	Lime, Anhydrite & Shale.
8-22-68	Marmaton 4044	3439 - 3749	Lime & Shale.
8-23-68	Cher. 4578	3749 - 3939	Lime & Shale.
8-24-68	Ataka 4710	3939 - 4180	Lime & Shale.
8-25-68	Marow 4858	4180 - 4539	Lime & Shale.
8-26-68	U. " 5033	4539 - 4234	Lime & Shale.
8-27-68	Mid. " 5036	4234 - 4872	Lime & Shale.
8-28-68	L. " 5143	4872 - 5070	Lime, Shale & Sand.
8-29-68	St. Hen. 5234	5070 - 5187	Lime & Shale.
8-30-68	St. L. 5299	5187 - 5322	Lime & Shale.
8-31-68	Speng. 5397	5322 - 5376	Miss. Lime.
		5376 - 5405	Lime & Shale.

CASING RECORD

8-18-68

Run 10 Jts. 8 5/8" casing, 9 Jts. 20#, and
1 Jt. 24#. Set at 401 K.B. Cemented w/125
sacks Common, 2% c.c., 200 sacks Common,
3% HA-5.

9-1-68

Set plugs at 125', 25', and 10'.