

19-19-5W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- TRANS ERA PETROLEUM, INC.
Farm- Myers No. 1

SEC. 19 T. 19 R. 5W
SW SW SE

Total Depth. 3982
Comm. 12-16-53
Shot or Treated.
Contractor.
Cased. 2-27-54

Comp. 1-7-54

County McPherson
KANSAS



CASING:

8 5/8" 186' cem. w/125 sx
5 1/2" 3490' cem. w/100 sx

Elevation. 1641 DE

Production. 400 BO & tr. wtr.

Figures indicate Bottom of Formations.

clay, sand, red bed	
& shale	120
sand, shale, shells	450
shale	530
shale, a nhydrite	
streaks	584
shale	610
salt, shale	850
sand hrd, shale	980
shale, shells	1060
shale, lime	1240
lime	1540
shale, lime	2460
lime	2564
lime, shale	2595
lime	2730
shale, lime	2805
lime	2992
shale, lime	3048
lime	3088
lime, shale	3402
miss. chat	3425
chat	3459
chat, dolomite	3499
chert	3522
lime, shale	3545
chert, lime	3582
shale	3829
dolomite	3839
dolomite, lime	3851
lime	3876
simpson	3896
sand, pyrite	3952
lime	3982
Total Depth	

Scout Tops:

Lansing	2801
Conglomerate	3404
Miss. Chat	3420
Maquoketa	3832
Viola	3841
Simpson	3863
Arbuckle	3944