


ALLISON-FITZWILLIAM PETRO. CORP.
Fulton No. 1SEC. 24 T. 19 R. 6W
NWc NETotal Depth. 4002'
Comm. 2-22-37 Comp. 6-13-37
Shot or Treated.
Contractor. Allison-Fitzwilliam Petro. Corp.
Issued. 6-26-37

County. Rice



CASING:

20"	55'	8 1/4"	2835'
12 1/2"	415'	6 5/8"	3524'
10"	2260'		

Elevation. 1617

Production. Dry

Figures Indicate Bottom of Formations.

cellar	10	shale & shells	1600	lime hrd	2616
clay	20	lime	1620	lime HFW 2630-40	2630
gumbo	40	shale blue	1625	sdv lime	2650
shale blue	70	lime	1645	lime	2655
red rock	150	lime brkn	1660	shale blue	2660
shale light	160	shale blue	1665	lime brkn	2669
shale	185	lime 2 BW 1645-60	1700	shale	2690
shale blue	200	shale	1715	sand	2710
red rock	235	shale blue	1720	shale drk	2720
shale brown	280	lime	1725	shale blue	2742
shale blue	505	shale	1735	shale drk	2755
shale	580	lime	1750	shale blue	2768
salt	645	shale blue	1780	shale	2800
shale blue	648	lime	1785	lime	2803
salt	700	shale	1820	shale blue	2833
shale blue	705	lime	1825	lime K.C.	2838
salt	840	shale blue	1835	lime	2855
shale blue	855	lime	1845	brkn lime	2865
salt	895	red rock	1850	lime	2870
shale blue	935	lime	1860	shale blue	2874
lime	950	shale blue	1870	lime	2880
shale blue	955	lime	1875	wtr sand HFW 2880-88	2888
lime	960	shale blue	1890	lime sdv	2900
shale blue	965	red rock	1900	lime sft W	2947
lime	975	shale blue	1925	lime	2994
shale blue	1025	lime	1930	shale blue	2996
shale & lime shells	1050	shale blue	1950	lime	3000
lime	1070	lime	1960	shale	3005
shale light	1075	shale	1970	lime	3040
shale blue	1080	shale blue	1995	sdv lime	3045
lime	1115	lime sdv	2010	lime	3070
shale blue	1120	shale blue	2025	sand W	3080
lime white	1125	lime	2060	sdv lime HFW 3075	3112
shale blue	1130	shale	2065	shale blue	3114
red rock	1155	shale blue	2075	shale	3122
lime	1195	lime	2080	lime	3145
shale blue	1200	shale blue	2085	shale blue	3149
lime 1/2 BW 1230-40	1230	lime grey	2095	shale	3164
brkn lime	1265	shale blue	2105	lime	3188
lime grey	1285	red rock	2110	shale	3193
red rock	1295	shale	2120	shale blue	3195
lime grey	1310	lime 1/2 BW 2120-30	2130	lime	3198
shale blue & lime shells	1335	shale blue & lime		shale	3218
lime	1355	shells	2150	lime	3230
shale blue	1365	lime	2170	red rock	3235
lime	1380	shale blue	2195	lime brkn	3240
lime grey	1385	lime	2260	lime	3252
shale blue	1390	shale blue	2265	slate blk	3257
red rock	1400	lime brkn HFW 2290	2290	shale	3270
lime	1410	sand	2300	lime	3285
shale	1420	lime	2345	shale blue	3290
shale blue	1425	lime & shale breaks	2351	lime brkn	3300
lime	1430	lime	2410	slate grey	3315
shale blue	1435	shale	2420	lime brkn	3325
lime	1450	lime	2475	sdv lime	3335
shale blue	1455	lime & shale	2482		
red rock	1460	lime	2534		
lime	1465	shale blue	2540		
shale & shells	1500	lime	2590		
lime	1540	shale blue	2595		
red rock	1545	lime	2599		
lime	1560	shale blue	2608		
lime, shale breaks	1590	shale black	2614		

(OVER)

Chat 3450? sc4
1617
-1833

2835
1617
-1218
3920
1617
-2303

red rock	3335-43
lime 5 BW 3320-30	3348
red rock	3360
shale VC	3365
lime brkn	3380
shale & lime shells	3400
conglomerate	3405
shale VC	3457
shale 8 BW 3450-57	3465
lime sdy	3495
chert	3512
shale green	3515
lime	3550
shale blue	3600
shale	3655
shale blue	3720
shale	3768
shale blue	3788
lime sdy	3794
lime	3870
shale blue	3880
shale	3910
sand	3927
lime	4002

HFV 3995-4002

Total Depth.