


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

SHADE & BERRY
Mattson No. 1

SEC. 25 T. 19 R. 6 W.
CSW SE
660' N of SL. 515' E of WL
of SW SE

Total Depth. 3381
Comm. 5-3-42 Comp. 5-21-42
Shot or Treated. No
Contractor. Campbell Drilling Co.
Issued. 6-20-42

County Rice.



CASING.

85 $\frac{1}{8}$ " 176' cemented.
5 $\frac{1}{2}$ " 3356' cemented.

Elevation.

Production. Pot. 260 B.
Pump.

Figures Indicate Bottom of Formations.

cellar	10
clay and shells	50
shale shells and sand	250
shale and shells	505
salt and shale	750
shale and shells	860
anhydrite and shale	1050
shale and shells	1070
lime and sand	1190
broken lime, sand & shale	1300
shale and sand	1585
broken lime and shale	1745
shale and lime	2510
lime	2645
lime and shale streaks	2795
broken lime and shale	2845
lime soft	2898
lime and shale	2910
lime	3087
lime and shale strks	3137
lime and shale	3272
shale and lime streaks	3329
chert (false chat)	3331
shale	3348
chat	3352

T.D. Rotary & Measurements
from top Rotary table.

Corrected SLM Meas. and Corrected
to derrick floor.

Top Chat	3353-	3357
----------	-------	------

CABLE TOOLS.

chat	3356-	3381	Oil.
------	-------	------	------

Total Depth.

Potential taken -May 25, 1942 260 B. Pump.