


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

WESTGATE-GREENLAND OIL CO.  
Smyres No. 1.

SEC. 36 T. 19 R. 6 W  
NE SE SW

Total Depth. 3359  
Comm. 3-6-42 Comp. 4-3-42  
Shot or Treated.  
Contractor.  
Issued. 4-25-42

County Rico.



CASING.

10" 150' cemented.  
7" 3338'

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations.

|                             |      |
|-----------------------------|------|
| surface clay and sand       | 50   |
| shale and shells (11" hole) | 155  |
| shale and shells            | 405  |
| shale and shells            | 763  |
| shale and lime shells       | 830  |
| anhydrite                   | 860  |
| shale and broken lime       | 928  |
| shale and lime              | 1100 |
| sharp sdy lime              | 1228 |
| sdv lime                    | 1240 |
| lime and shale              | 1425 |
| lime                        | 1505 |
| lime                        | 1675 |
| lime and shale              | 1955 |
| shale and lime shells       | 2065 |
| shale and lime              | 2166 |
| lime                        | 2203 |
| shale                       | 2240 |
| lime                        | 2703 |
| shale                       | 2741 |
| sticky shale                | 2745 |
| shale and lime              | 2872 |
| shale                       | 2905 |
| lime                        | 2952 |
| lime hard                   | 2998 |
| lime                        | 3192 |
| lime                        | 3245 |
| shale                       | 3262 |
| shale and broken lime       | 3304 |
| shale and lime shells       | 3336 |
| chat                        | 3339 |
| chat - - oil pay            | 3344 |
| chat                        | 3359 |
| Total Depth.                |      |