

7-19-2W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GEORGE HESS & LARRY MOORE RANCH INC.
Farm- Inez Hill No. 1

SEC. 7 T. 19 R. 2W
C S/2 NW
1320' E of WL, 660' N OF SL

Total Depth. 3058' PB 2425'
Comm. 2-10-58 Comp. 2-17-58
Shot or Treated.
Contractor. Mallard Drlg.
Issued. 5-3-58

County McPherson
KANSAS



Elevation. 1559' Est.

Production. 20 BOPD

CASING:

8 5/8" 166' cem w/110 sx.
5 1/2" 3000' cem w/125 sx.

Figures Indicate Bottom of Formations.

sand	70
shale	610
lime & shale	800
lime	985
shale	1400
shale & lime	1870
lime	2020
shale & lime	2347
K.C. lime	2385
lime	2660
shale & lime	2760
lime	2895
shale & lime	2997
shale	3012 RTD
shale	3058

Total Depth

Plugged back to 2425'

water & oil 3052-58'

TOPS:

Kansas City Lime	2347
Mississippi	2997

Perf. 30 holes, 2351-2361, acid 500 gal.

Meas. taken from R.D.B. R.D.B. 5½'
from ground level.