

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


Entered - J. 115.
35-19-8W

ATLANTIC REFG. CO.
Brubaker No. 1.

SEC. 35 T. 19 R. 8W
CSL NW SE
100' N of C W/2 SE

Total Depth. 3307'
Comm. 10-1-40 Comp. 10-30-40
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 12-7-40

County. Rice



CASING:
10 $\frac{3}{4}$ " 263'
5 $\frac{1}{2}$ " 3307'

Elevation.

Production. Pet. 8,787,000 G.

Figures Indicate Bottom of Formations.

surface blk	60
shale sdy	110
shale & shells	231
shale & lime sdy	270
shale & shells	335
anhydrite	380
shale & shells	780
salt	1050
shale & shells	1085
shale & lime shells	1196
shale & sand	1222
shale & shells	1425
lime	1465
shale & lime	1540
lime brkn	1780
shale & shells	2140
lime brkn	2325
shale & shells	2365
lime brkn	2465
lime	2500
lime brkn	2540
lime	2550
shale & strks lime	2664
lime	2711
shale	2743
shale & lime	2795
lime	2847
shale & lime	2993
lime hrd	3020
lime sft	3037
lime med	3061
lime	3153
lime brkn & shale	3171
chert & lime	3200
conglomerate	3205
lime Viola	3240
lime	3255
pyrite & hrd sand	3260
shale & lime	3298
lime	3307
Total Depth.	

10-20-40 Lane-Wells Gun
3250-68 - 60 shots
10-21-40 Lane-Wells Gun
3294-3300 - 24 shots