

35-19-8W

987

ATLANTIC REFG. CO.  
Pulliam No. 1-B.

SEC. 35 T. 19 R. 8W  
CWL S/2 NE

Total Depth. 3277'

County. Rice

Comm. 8-21-38 Comp. 9-14-38


OCT 8 1938

Shot or Treated. Not shot or acidized.

Contractor. Simpson & Noble Drlg.Co.

Issued. 10-8-38

Rotary with cable  
tool completion.



CASING:

10 3/4" 200'6"  
7" 3246'

Elevation.

Production. Pot. 51,000,000 G.

Figures Indicate Bottom of Formations.

clay	20
sand	78
sand rock hrd	92
shale & sand	200
rod bed	260
sand rock	280
red bed	360
anhydrite	400
red bed & shells	517
red bed	525
anhydrite	530
shale & shells	1070
salt	1100
brkn lime	1844
shale & shells	2304
brkn lime	2440
lime	2620
lime brown	2676
lime brkn	2710
conglomerate	2745
sdv shale & lime shells	2760
shale & lime shells	2843
lime brkn	2887
lime	3111
lime brkn	3150
conglomerate	3197
shale	3205
sand hrd	3214
shale	3248
Core #1 - 3' rec 3248-51	
sand	3249
lime	3255
Core #2 3255-73	
Core #3 - 3' rec 3273-79	
very porous dolomite	
carrying gas SIM 3279=3277	
Total Depth	