

35-19-8W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL COMPANY
Farm- Wright "B" No. 1

SEC. 35 T. 19 R. 8W
C NW NW

Total Depth. 3568'

Comm. 12-30-64

Shot or Treated.


Contractor. Imperial Oil

Issued. 3-6-65

Comp. 1-10-65

County Rice

KANSAS



Elevation. 1717' KB

Production. Dry

CASING:

8 5/8" 1170' cem w/550 sx

Figures Indicate Bottom of Formations.

shale	276
Anhydrite	288
shale - shells	365
shale red bed	525
hard sand & pyrite	530
shale & red bed	652
shale - shells	1170
snale - lime	1500
lime - shale	1650
shale - lime	2215
lime	2410
lime - shale	2956
lime	3345
lime - shale	3428
lime	3568
Total Depth	3568

TOPS: SAMPLE

Heebner	2739
Brown Lime	2880
Lansing	2912
Base of Kansas City	3218
Kinderhook Lime	3309
Kinderhook Shale	3328
Kinderhook Sand	3448
Viola	3456
Simpson Shale	3512
Arbuckle	3548

TOPS: LOG

Heebner	2740
Brown lime	2879
Lansing	2913
Base Kansas City	3218
Kinderhook Lime	3307
" Shale	3326
" Sand	3447
Viola	3453
Simpson Shale	3511
Arbuckle	3549

DST #1 3448-58

(straddle Test) Opn 30" Weak blow

dead in 5 Min. Rec. 35' mud. ICI 1163#/20"

IF 19#, FF 19#, FBHP 1084#/20".