

34-19-8W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- WESTERN PETROLEUM CO.  
Farm- Stockham No. 1

SEC. 34 T. 19 R. 8W  
C NE NE

Total Depth. 3493'  
Comm. 10-29-64 . Comp. 11-9-64  
Shot or Treated.  
Contractor. Western Pet. Co.  
Issued. 2-13-65

County Rice  
KANSAS



Elevation. 1721' KB

Production. 41 BOPD 15% Wtr

CASING:

3 5/8" 222' cem w/ 185 sx  
5 1/2" 3440' cem w/ 100 sx

Figures Indicate Bottom of Formations.

clay	40
shale	150
red bed	268
anhydrite	285
red bed, sand, shale	716
shale, shells	1260
lime & shale	3080
lime	3232
lime & shale	3350
shale, sand, lime	3410
shale & lime	3446
lime & shale	3465
lime	3493 RTD
Total Depth	

TOPS: LOG

Anhydrite (smp)	283
Heebner	2731
Toronto	2754
Dougals	2768
Iatan	2868
Lansing	2903
Base Kansas City	3202
Kinderhook	3236
Kinderhook sand	3344
Maquoketa	3349
Viola	3353
Simpson	3398
Arbuckle	3455

DST #1 3318-50' Op 1 hr and 15 min,  
strong blow; Rec. 1140' visible gas, 430'  
fluid estimated @ 70' slightly oil cut  
mud, 120' muddy oil, no apparent water.  
IBHP 1113# 30 min.; FBHP 1054 # 30 min;  
IFP 57#, FFP 144#, HH 1856#

ran Welex Neutron, gamma ray and caliper logs