


CONTINENTAL OIL CO.
J.B. Connery No. 1-A.

SEC. 1 T. 19 R. 8W 1-19-8W
NEc NE
330' S 330' W NEcor.

Total Depth. 3258'
Comm. 12-9-37 Comp. 1-16-38
Shot or Treated. 2000 Gals.
Contractor.
Issued. 2-26-38

County. Rice

FEB 26 1938



CASING:
10 3/4" 200'
7" 3250' 6"

Elevation.

Production. Pot. 962.10 B.
153 BW

Figures Indicate Bottom of Formations.

surface	80	
shale & red rock	425	
shale & shells	750	
salt	1050	
shale & shells	1190	
shale	1225	
brkn lime	1650	
shale & shells	2380	
lime	2555	
brkn lime	2715	
shale & shells	2790	
brkn lime	2865	
lime	2922	
lime sft	2956	
lime	3190	
conglomerate	3207	
sand	3216	
lime	3220	
chert & shale	3232	
shale	3252	Top of Arbuckle lime 3250'
lime Arbuckle	3255	
lime	3257	
lime	3258	
Total Depth.		

1-5-38 well pumped 238 B.O., 7 hrs.
Acidized 2000 Gals.
1-9-38 Pot. 225.84 bbls 1st 4 hrs and
201 bbls oil last 3 hrs, 48 BW in
7 hr.-test.
1-13-38 on initial potential test
well pumped 160.35 bbls oil and 32
bbls wtr and 169.74 bbls oil and
19 bbls wtr last four hrs, giving
well a 24-hr potential of 962.10
bbls oil and 153 bbls wtr.