

26-19-8W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL COMPANY
Farm- Smith No. 1

SEC. 26 T. 19 R. 8W
SE SW SE

Total Depth. 3490'
Comm. 12-21-64 Comp. 12-29-64
Shot or Treated.
Contractor. Imperial Oil
Cased. 3-20-65

County Rice KANSAS



CASING:
3 5/8" 243' cem w/165 sx.

Elevation. 1728 KB

Production. Dry

Figures Indicate Bottom of Formations.

shale-sand	242
shale - red bed	390
shale, - shells	1030
salt - shale	1368
lime - shale	1665
shale - lime	1830
shale	2160
lime & shale	2900
lime	3322
lime-shale	3390
lime & chert	3410
lime & chert "hard"	3417
lime & shale	3487
lime	3490
Total Depth	3490

TOPS: Log	
Top of Anhydrite	270
Heebner	2703
Brown Lime	2839
Lansing	2875
Base Kansas City	3187
Kinderhook	3223
Viola	3350
Simpson	3385
*Arbuckle	3448

*Sample

DST # 1 3378-90 Op 2 hrs, Rec. 75' muddy salt water. ICIP 918# 20min, If 19#, FF 38#, FCIP 849# 20 min.

DST # 2 Miss-run

DST # 3 3410-90 Op 30 min. Rec. 2460' salt water. ICIP 1153# 20 min, IF 888, FF 1153#, FBJP 1153# 20 min.