


14-19-9w

SHELL PETRO. CORP. (COMMUNITY)
 E. M. Pichler No. 1-A.

SEC. 14 T. 19 R. 9W
 NWc NW
 440' fr NL 330' fr WL NW $\frac{1}{4}$

Total Depth. 3279'
 Comm. 8-31-38 Comp. 9-25-38
 Shot or Treated.
 Contractor. Crow Drlg. Co.
 Issued. 11-5-38

County. Rice



NOV 5 1938

CASING:
 7" 232'
 4 $\frac{1}{2}$ " 3274'

Elevation.

Production. Pot. 1110 B.
 273 BW

Figures Indicate Bottom of Formations.

soil & sand	40
shale & shells	234
shale red	338
shells	358
anhydrite	372
shale & shells	842
salt	1029
shale & lime strks	1140
lime	1146
shale	1155
anhydrite	1178
shale	1209
lime	1289
anhydrite	1315
dolomite	1369
lime	1380
shale	1430
brkn lime	1496
chert & lime strks	1521
lime	1603
shale	1615
lime	1655
brkn lime	1676
lime	1690
brkn lime	1740
shale & lime strks	1815
lime & shale	1950
shale	2020
shale & lime strks	2084
lime	2093
shale	2143
lime	2158
shale	2230
lime	2242
brkn lime	2311
shale	2324
lime, shale strks	2370
shale	2395
lime	2414
brkn lime	2426
sdv lime	2466
lime	2597
sdv lime	2611
lime	2641
brkn lime	2647
lime	2723
lime, shale strks	2771
lime & shale	2843
shale	2898
lime	2920
sdv lime	2925
lime	2977

trace very poor oil stain

lime 3072

fair oil stain

sm amt oil 2989-98

Core #1 3273-78

trace oil stain

bleeding some wtr

SL Correction 3278 equals 3279

dolomite 3279 Total Depth.