

6-19-9W

SHELL PETRO.-COMMUNITY

J. Hafermann No. 2

DEEPENING RECORD.

SEC 6 T. 19 R. 9W

Cen SE $\frac{1}{4}$ 1300' fr S.L. 1300' fr E.L.
SE $\frac{1}{4}$

Total Depth. 3835


Comm. 8-5-36 Comp. 9-19-36

Shot or Treated.

Contractor. Haynes Drlg Corp.

Issued. 1-29-38

County Rice.



CASING.

13" 150'
7" 3220'
5" 3314'

JAN 29 1938

Elevation.

Production. Pot. 92 B.O.
4 B.W.

Figures Indicate Bottom of Formations.

clay, shale, sand and		dolomite	3250
lime shells	162	dolomite & shale green	
shale red bed and lime			3252
shells	362	dolomite chert&shale	3254
shale and shells	529	dolomite	3260 $\frac{1}{2}$
shale and lime	808	dolomite small amount	
shale & anhydrite	827	of green shale	3262
salt	1117	dolomite-chert	3264
shale and lime	1272	dolomite	3266
shale and shells	1357	dolomite trace green	
lime and shale	1643	shale	3268
sand and shale	1709	dolomite	3270
shale lime shells	1784	Total Depth.	
lime and shale	1922		
shale & lime shells	2030	Plugged back dolomite	3263 $\frac{1}{2}$
lime and shale	2380		
sand and shale	2392	DEEPENING RECORD.	
lime and shale	2446	Old T.D.	3270
lime	2500	P.D. to dolomite	3261
shale and lime	2513	Comm. 10-29-37	
lime and shale streaks	2654	Comp. - 12-31-37	
lime and shale	2734	Prod. - Salt wtr Disposal	
lime and shale	2752		
shale	2776	drilling load wool	3270
lime	2795	dolomite	3578
shale and lime	2856	shale	3582
lime hard	2864	dolomite	3593
lime soft	2866	shale	3602
lime with shale strks	2875	dolomite	3730
slight odor gas in samples		dolomite sdy	3738
2885-2900		3738 equals 3735 SLC	
lime	2936	dolomite sdy	3740
lime	2952	sand	3756
lime grayish	2953	Granite wash	3835
lime grey & shale	2957	Total Depth.	
lime	3040		
lime shale streaks	3055		
lime	3088		
lime shale streaks	3130		
lime	3132		
shale and lime	3190		
3190 equals 3187 S.L.C.			
conglomerate&lime and			
shale reddish brown and			
grayish green	3195		
conglomerate and shale			
dark reddish brown some			
green	3210		
shaley sand greenish			
shale	3215		
sdv shale reddish brown			
and green	3220		
dolomite & shale	3225		
3225 equals 3224 Derrick			
Floor Meas.			
dolomite	3224		
dolomite	3226		
dolomite some pale			
green shale	3232		
dolomite	3235		