

6-19-9W hook

SHELL PETRO.-(COMMUNITY)  
 J. Hafermann No. 3

SEC. 6 T. 19 R. 9W.  
 NEc SE  
 330' fr NL 330' fr EL SE $\frac{1}{4}$


Total Depth 3238  
 Comm. 10-22-36 Comp. 11-27-36  
 Shot or Treated. 2000 gal acid.  
 Contractor. Haynes Drlg. Corp.  
 Issued. 12-19-36

County. Rice.

CASING:

13" 149'  
 7" 3218'  
 5 $\frac{1}{2}$ " 3238'

DEC 19 1936



Elevation.

Production. Pot. 2189 D.  
 no wtr.

Figures Indicate Bottom of Formations.

clay shale sand & lime shells	160
shale and shells	400
shale and lime shells	605
shale and shells	838
salt	1089
salt and shale	1156
shale and lime shells	1240
shale and shells	1278
lime	1325
shale and lime	1471
lime broken	1515
shale and lime	1579
shale and lime	1885
shale and broken lime	2011
shale and lime	2175
shale and lime streaks	2265
sdv lime	2281
broken lime	2290
lime and shale	2399
broken lime	2448
lime	2530
lime and shale streaks	2654
lime	2714
lime and shale	2742
2742 equals 2745	
shale and lime	2820
lime and shale streaks	2874
lime	2947
little gas showing at 2897	
lime grey grey to brownish grey soft	
conglomeratic	2952
lime grayish brown streaks shale	2957
lime soft	2967
lime grayish brown	3041
shale and lime streaks	3088
shale and lime	3115
lime	3144
lime and shale	3194
conglomerate lime	3199
lime hard	3204
shale pale green brownish red	3209
shale pale green	3216
shale dark green	3218 $\frac{1}{2}$
small amount free oil.	
dolomite light brownish grey	3219
dolomite	3238 Total Depth.