

10-14-9w


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKILES OIL CORP. & EARL F. WAKEFIELD
Farm- Soeken "A" No. 1

SEC. 10 T. 19 R. 9W
NW SW NW

Total Depth. 3278
Comm. 8-26-52 Comp. 10-2-52
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 10-25-52

County Rice KANSAS



CASING:
15 1/2" 53' P. 8 5/8" 2205' P.
13 3/8" 349' P. 7" 2980' P.
10 3/4" 1755' P.

Elevation. 1704
1706 (road)
Production. Dry

Figures Indicate Bottom of Formations.

cellar	8	shale blue	1710	lime	2737
clay	15	lime	1740	shale	2750
yellow sand	45	red rock	1754	lime	2761
shale blue	50	lime	1760	shale	2855
sand	55	red rock	1765	lime	2857
shale yellow	75	lime	1777	shale	2875
5 BWPH	90	shale drk	1781	red rock	2878
sand	115	lime	1795	shale	2882
shale blue	175	2 1/2 BWPH 1800-1810'		show of oil 2910	
sand	190	shale	1810	lime	2950
red rock	344	shale & shells	1830	shale	2952
chalk	346	red rock	1836	3 BWPH 2968-2978'	
lime	360	lime	1865	lime	3030
shale blue	365	shale & shells	1875	shale	3035
red rock	625	lime	1898	lime	3087
shale blue	680	shale	1904	shale	3090
red rock	705	lime	1914	lime	3152
shale	720	shale	1918	shale	3155
red rock	735	lime	1920	lime	3202
shale blue	840	shale	1930	congl.	3225
salt	1135	lime	1935	6 1/2 BWPH 3232-3238	
shale blk	1145	shale & shells	1985	lime	3241
lime	1155	shale	1992	4 BWPH 3235-3237	
shale gry & shells	1215	gas 1995-2005'		conglomerate	3250
lime	1230	sandy shale	2005	shale	3276
shale	1235	lime	2012	water 3276-3278	
lime	1238	shale & shells	2070	lime	3278
shale	1242	red rock	2075	Total Depth	
lime	1250	shale	2090	Scout Tops:	
shale & shells	1275	sandy shale	2135	Anhydrite	346
red rock	1280	lime	2147	Lansing	2882
lime	1312	shale	2165	Conglomerate	3202
shale	1326	7 BWPH 2165-2175		Arbuckle	3276
lime	1330	sandy shale	2199		
shale & shells	1335	lime	2235		
lime	1370	shale	2245		
shale brown	1375	lime broken	2265		
red rock	1385	shale	2275		
1/4 BWPH 1430-1435		lime	2280		
lime	1485	shale	2285		
2 BWPH 1500-1510		lime	2315		
lime	1530	shale & shells	2328		
shale & shells	1570	gas	2328		
lime	1580	sandy lime	2330		
shale	1582	sandy shale	2355		
lime	1590	lime	2365		
shale	1598	shale	2370		
lime	1630	lime	2385		
shale	1635	shale	2393		
red rock	1645	lime	2425		
lime	1650	shale & shells	2455		
shale	1655	1 BWPH 2490-2500			
lime	1660	lime	2555		
shale	1665	shale	2560		
red rock	1670	show of oil 2673-2675			
lime	1695	lime	2726		
		shale drk	2730		