

6-19-9W

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-159-05706

Company - CITIES SERVICE OIL CO.
Farm - Willard "A" No. 1 ✓

SEC. 6 T. 19 R. 9 W
SE NE SW
990' S & 330' W of Contor

Total Depth. 3233' FB 3196'
Comm. 4-7-47 Comp. 4-19-47
Shot or Treated. 1000 gals. 5-3-47
Contractor. Corbott-Barbour Drlg. Co.
Issued. 7-5-47

County. Rico
KANSAS



CASING:

8 5/8" 305' Com. w/125 sx.
5 1/2" 3231' Com. w/150 sx.

Elevation. 1709 Act & h.

Production. Phy. Pot. 546 BO,
41.5 wtr., 24 hrs.

Figures Indicate Bottom of Formations.

sand, shalo & shells	0-305
shalo & shells	960
salt & shalo	1155
shalo & shells	1250
lime sdy	1475
limo	1605
shalc & limo	1695
limo brkn	1845
shalc & shells	2390
limo & shalc	2550
limo	2715
shalo & limo	2810
limo	2827
shalc	2887
limo	3210
shalo	3226
limo	3229
3229= 3233'SLM	
Total Dophth.	3233 SLM

Tops:
Lansing 2876 Corr.
Arbuckle 3230 Corr.
Penetration 3'

Drl'd Cement to 3196'SLM
Perf. 11 shots 2955-66'
Perf. 35 shots 2966-74'

1470' fluid in 2 hrs.
Hole full oil & flow in
9 hrs.