

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


6-19-9W

Company- CITIES SERVICE OIL
Farm- Willard "A" No. 4

SEC. 6 T. 19 R. 9W
NE NE SW

Total Depth. 3720'
Comm. 8-21-50 Comp. 9-4-50
Shot or Treated.
Contractor. R. W. Rine Drig.
Issued. 2-25-61

County Rice
KANSAS



CASING:
5 1/2" 3307' cem w/200 sx.

Elevation. 1711'

Production. SWDW

Figures indicate Bottom of Formations.

Cleaned out abandoned well to 2297'
top of 7" casing. Cleaned out to 2577'
inside 7" casing and found junk in hole.

Set whipstock 2270-2297 and cemented
with 200 sacks; top of cement 2073.

Drilled out of old hole at 2130'

lime & shale	2130-2290
shale & lime	2510
lime	2555
lime & shale	2710
lime	2765
lime & shale	2870
lime	2955
shale & lime	3035
lime	3369
lime & chert	3412
lime	3542
lime & chert	3582
lime	3705
quartzite	3720
Total Depth	

TOPS:
Lansing 2875
Arbuckle 3242
Quartzite 3705
Penetration 15'

Jet acidized 3000 gals. 3310-3700.