

6-19-4W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas


Company - **CITIES SERVICE OIL COMPANY**
Farm **Willard "A"** No. **2**
Willard

SEC. **6** T. **19** R. **9W**
SW NW SW

990' S & 830' E of W/4 Cor.
330

County. **Rice**

KANSAS



Total Depth. **3234 = 3229 SLM**
Comm. **10-30-47** Comp. **11-9-47**
Shot or Treated. **Acid. 500 gals. 11-21-47**
Contractor. **Corbett-Barbour Drilling Co.**
Issued **2-21-48**

CASING:

8 5/8" 260' cem 150 sx.
5 1/2" 3226' cem 150 sx.

Elevation. _____

Production. Gauge Pot.: 2901 B0

Figures indicate Bottom of Formations. no wtr, 2 1/2 hrs. B.H.P. 930#

shale & sand	95
shale, sand & shells	175
shale	210
shale & shells	260
red bed	355
anhydrite	385
shale & shells	1020
shale	1165
shale & lime	1450
shale, sand & shells	1530
lime	1545
lime & shale	1680
shale & lime	1795
lime & shale	1825
shale & lime	2455
shale	2500
lime	2780
shale	2882
lime	3214
shale	3223
conglomerate	3231
lime	3234

3234 3234 Rot. TD - 3229 SLM

Total Depth

TOPS:

Corr. Top Lansing 2877'
Corr. Eros. Arbuckle 3218'
Corr. Arbuckle 3226'
Penetration 3'
Total Depth. 3229'

Drilled cement to 3181 SLM

Perf. 50 shots 2955-67
spray oil in 20 mins.
Flowed head in 1 hr. 10 min.