

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


6-19-9W

Company- CITIES SERVICE OIL CO.  
Farm- Behnke Unit, Tract No. 5-W  
#2

SEC. 6 T. 19 R. 9W  
NW NW SW  
330' S & 330' E of W/4 Corner

Total Depth. 3253' PB 3230'  
Comm. 11-18-60 Comp. 11-26-60  
Shot or Treated.  
Contractor. Peel Bros., Inc.  
Issued. 3-18-61

County Rice  
KANSAS



Elevation. 1714' DF

Production. 3 BO, 45 BW/24 hrs.

CASING:

8 5/8" 297' cem w/240 sx.  
4 1/2" 3252' cem w/200 sx.

Figures Indicate Bottom of Formations

shale & shells	195
shale & red bed	297
shale & shells	370
Anhydrite	405
shale & shells	1255
lime	1385
lime & shale	1610
lime	1725
lime, shale & shells	1900
lime & shale	2230
shale & lime shells	2405
shale & lime	2430
lime	3255

3255 RTD = 3253 SLM

Total Depth  
Plugged back to 3230'

TOPS: SCOUT	
Lansing	2898
Conglomerate	3236
Arbuckle	3250