

33-19-9w


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETRO. CORP.
Farm - Purcell No. 1

SEC. 33 T. 19 R. 9W
NEc NW

Total Depth. 3274
Comm. 8-5-46 Comp. 8-26-46
Shot or Treated.
Contractor. Beardmore Drlg. Co.
Issued. 9-14-46

County. Rice
KANSAS



Elevation. 1693^{sh}

Production. Dry

CASING:

8 $\frac{1}{4}$ " 191'
5 $\frac{1}{2}$ " 3220'

Figures Indicate Bottom of Formations.

surface clay	30
sand	60
shale & shells	191
red rock	300
anhydrite	325
shale & shells	900
salt & shale	1100
shale & shells	1300
shale & lime	1500
lime brkn	1815
shale & limo	2025
shale	2160
shale & shells	2380
shale & lime	2700
lime	2725
shale & lime	2858
lime	2915
limo brkn	3204
conglomerate- lime	3220
limo	3251
lime brkn	3253
limo	3269
lime brkn	3274
Total Depth	

Tops:

Anhydrite	300
Lansing	
Arbuckle	3214

DP & DD 3245 VSSO
DD 3251 no incr. 500 Acid no results
DD 3262 600' Wtr. Swb. till wtr
exhausted.
DD 3269 1000 Acid. no help.
DD 3274 TD