

28-19-9W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY THE CARL TODD DRLG. CO.

SEC. 28 T. 19 R. 9W

FARM Callis

NO. 1

LOC. NE NE SW

TOTAL DEPTH 3257

COMM. 4-1-51

COMP. 4-14-51


SHOT OR TREATED

CONTRACTOR The Carl Todd Drlg. Co., et al

ISSUED 6-9-51

COUNTY Rice

KANSAS



CASING

8 5/8" 202' cem. w/130 sx

5 1/2" 3243' cem. w/75 sx

ELEVATION 1705 (m)
1707 R.B.

PRODUCTION Pmp. 114 BO

FIGURES INDICATE BOTTOM OF FORMATIONS

clay, shale	50
shale, sand	65
shale, shells	202
red bed, shells	315
anhydrite	340
shale, shells	850
shale, salt	1050
shale, shells	1170
lime, shale	1345
lime	1795
lime, shale	2585
lime	2795
shale, lime	2865
lime	3207
conglomerate	3241
arbuckle,	3257 RTD
Total Depth	

Tops: R.B.

Topeka	2469
Heebner	2742
Brown Lime	2870
Lansing	2895
Conglomerate	3207
Arbuckle	3241

DST: 3242-57, open 30 mins.
rec. 525' fluid, 225' clean
oil, 300' muddy oil, 850 lbs.
bottom hole pressure, 10 mins.

Drilled plug. Filled up 800'
in one hr. 15 mins. 1250' in
two hrs. 15 mins. 2900' in 24
hrs, no wtr. Put on pump.