

State Geological Survey
WICHITA, BRANCH

CONTRACTOR'S WELL LOG

15-147-20185
3-1-18W

OPERATOR: Leland R. Baird
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: WALKER #4
LOCATION: SE NW SW Section 3-1S-18W
Phillips County, Kansas
GEOLOGIST: Steve Powell
SPUD DATE: January 4, 1975
COMPLETION DATE: January 11, 1975

0	165	Clay & Sand
165	575	Shale
575	1295	Shale & Sand
1295	1370	Sand
1370	1657	Shale
1657	1660	Anhydrite
1660	2195	Shale & Sand
2195	2500	Shale
2500	3070	Lime & Shale
3070	3475	Lime
	3475	Rotary Total Depth

Drilled 206' of 12½" surface hole. Set 8-5/8" surface casing @206' K.B. Cemented with 150 sacks Quick-Set Cement. Cement circulated. Plug was down @9:00 p.m., January 4, 1975.

Set 4½" production casing @3471.77'. Cemented with 35 Sacks 50/50 Posmix, 2% gel, 12½# gilsonite per sack and 200 sacks Common, 18% salt and 2% gel. Plug was down @2:00 a.m., January 11, 1975.

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Jack K. Wharton, Geologist of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WALKER #4, SE NW SW, Section 3-1S-18W, Phillips County, Kansas

ABERCROMBIE DRILLING, INC.

By: Jack K. Wharton
Jack K. Wharton
Geologist

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 13th day of January, 1975.

Nancy E. Haner
Nancy E. Haner, Notary Public

My Commission Expires: April 8, 1978

