

OCT 3 1970

10-1-18W
C W/2 SW
(316) 267-0613

Ele. 2122' RB

B & B DRILLING, INC.
207 Petroleum Building
Wichita, Kansas 67202

May 15, 1970

~~RECEIVED~~
STATE CORPORATION COMMISSION
MAY 18 1970
CONSERVATION DIVISION
Wichita, Kansas

PMP 6080PD/nw
LKC

DRILLERS LOG

Co
Re: Leland R. Baird #1 Wittfoth
C W/2 Section 10-1S-18W
Phillips County, Kansas

OPERATOR: Leland R. Baird
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: May 6, 1970
COMPLETED: May 14, 1970
TOTAL DEPTH: 3575'

Set 8 5/8" @ 208' w/145 sx

0	209	Sand & Shale
209	259	Shale
259	1300	Shale & Sand
1300	1719	Sand & Shale
1719	1732	Anhydrite
1732	1825	Shale
1825	2126	Shale & Shells
2126	2495	Shale
2495	2612	Lime w/ Shale
2612	2804	Lime & Shale
2804	3145	Lime
3145	3376	Shale & Lime
3376	3420	Lime
3420	3492	Lime
3492	3575	Lime
3575		Total Depth

Log Logs
Tapeka 3097
Keebler 3287
Toronto 3320
LKC 3335
BKC 3558

DST #1 3376' - 3354'
DST #2 3378' - 3400'
DST #3 3398' - 3422'
DST #4 3440' - 3470'
DST #5 3470' - 3495'

Ran 5 1/2" casing set @ 3574' w/ 35 sx 50/50 Poz
12 1/2" Gilsonite - 155 sx Comm 2 1/2 gel 8-1 1/2 CFR-2

We certify the above and foregoing to be true and correct copy of the log on the #1 Wittforth, located in Phillips County, Kansas.



Zell Baker President

Alma A. Neuse Notary Public
Subscribed and sworn to before me this 15th day of May, 1970.

My commission expires May 31, 1970.