

17-1-18W

State Geological Survey
WICHITA BRANCH

CONTRACTOR'S WELL LOG

OPERATOR:	Baird Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	L & G #2
LOCATION:	C SE NW, Section 17-1S-18W Phillips County, Kansas
SPUD DATE:	7/01/81
COMPLETION DATE:	7/10/81

0	216	Clay, Shale & Sand
216	1575	Shale & Sand
1575	1946	Sand & Shale
1946	2073	Shale & Sand
2073	2273	Lime & Shale
2273	2692	Shale & Lime
2692	3315	Lime & Shale
3315	3542	Lime
	3542	Rotary Total Depth

Spud hole @ 11:45 a.m., 7/01/81. Drilled 217' of a 12 1/4" hole. Ran 7 joints of 8 5/8" 20# Casing set @ 216'. Cemented with 165 sx. of Class A 2% Gel, 3% c.c. Cement did circulate. Plug was down @ 4:30 p.m., 7/01/81.

3542' TD. Ran 88 joints of 4 1/2" 9 1/2# casing set @ 3540' with 25 barrels chemical flush, 35 sx. of posmix, 2% Gel, 2 1/2# Gilsinite per sack. Followed with 200 sacks of Class A, 3/4% CFR 2, 18% Salt. Plug was down @ 8:15 a.m., 7/10/81.

SAMPLE TOPS:

Anhydrite 1710' - 1736'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the L & G #2, C SE NW, Section 17-1S-18W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.