

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


9-1-25W

Company- GEOCHEMICAL SURVEYS
Farm- Jenkins No. 1

SEC. 9 T. 1 R. 25W
C NE SW

Total Depth. 3560'
Comm. 11-1-62 Comp. 11-7-62
Shot or Treated. No
Contractor. Murfin Drilling Co.
Issued. 2-2-63

County Norton
KANSAS



CASING:
8 5/8" 171' cem w/125 sx.

Elevation. 2341' KB

Production. DRY

Figures Indicate Bottom of Formations.

sand & shale	60
blue shale	173
shale & shells	950
sand & shale	1150
shale & sand	1625
red bed & shale	1854
anhydrite	1882
shale-shells-pyrite	2200
shale & shells	2290
shale & lime	2520
shale-lime shells	2700
shale-lime	2815
lime & shale	3095
lime	3212
shale & lime	3230
lime & shale	3275
lime	3400
shale & lime sand	3430
granite wash & Precambrian	3557 RTD
granite wash & Precambrian ?	3560
Total Depth	

TOPS: LOG	
Topeka	3010
Oread	3162
Toronto	3214
Lansing	3220
"B"	3248
"C"	3296
"D"	3328
"E"	3370
"F"	3396
Base Kansas City	3424
Cherokee	3500
Reagan	3516
Base Reagan	3522
Granite Wash	3532
Granite	3546