

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-1-25W

Company- CHAMPLIN OIL & REFINING  
Farm- Railsback No. 1

SEC. 15 T. 1 R. 25W  
C NW NE

Total Depth. 3608'  
Comm. 1-11-62 Comp. 1-21-62  
Shot or Treated.  
Contractor. E. F. Wakefield  
Issued. 5-5-62

County Norton  
KANSAS



CASING:  
10 3/4" 225' cem w/250 sx.

Elevation. 2403' DF

Production. Dry

Figures Indicate Bottom of Formations.

soil, clay, sdy.	58
shale & lime	231
shale & shells	1350
shale	1400
sand	1460
shale & shells	2115
lime & shale	3260
lime	3290
lime & shale	3483
lime, shale & sand	3565
sand	3576
shale & lime	3608
Total Depth	

TOPS: SCOUT

Topeka	3112
Heebner	3238
Toronto	3272
Lansing	3279
Base Kansas City	3500
Basal Sand Zone	3563
Granite Wash	3573

DST #1 3236-3290', op 2 hrs, good blow  
for 1 hr, decreased 2nd hr. Rec. 960'  
muddy salt water, no show. ISIP 1204#/30 min,  
FSIP 1148#/60 min, IFP 94#, FFP 512#,  
IHP 1763#, FHP 1739#. BHT: 123 deg. F.

DST #2 3438-3483', op 1 hr, very weak blow  
for 13 mins, flushed tool, very weak blow  
for 3 min. Rec. 54' dr. mud, no show.  
ISIP 236#/30 min, FSIP 149#/60 min., IFP 27#,  
FFP 35#, IHP 1779#, FHP 1763#, BHT 114 deg. F.

DST #3 3521-3576', op 2 hrs, very weak blow  
for 7 min. Rec. 30' dr. mud, no show.  
ISIP 204#/30 min, FSIP 102#/60 min.,  
IHP 54#, FFP 54#, IHP 1892#, FHP 1859#.