

Duplicate
CONTRACTOR'S WELL LOG

15-039-20407

5-1-26W

OPERATOR:	Tracey Enterprises, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Atherton #2
LOCATION:	C SW SW Section 5-1S-26W Decatur County, Kansas
SPUD DATE:	February 17, 1978
COMPLETION DATE:	February 26, 1978

0	275	Surface soil, sand & shale
275	650	Shale
650	1930	Shale & sand
1930	1972	Shale
1972	1999	Anhydrite
1999	2515	Shale
2515	3066	Lime & shale
3066	3231	Shale
3231	3295	Lime
3295	3340	Shale
3340	3395	Lime
3395	3480	Shale & lime
3480	3580	Lime
3580	3585	Sand
3585	3590	Lime & sand
3590	3595	Sand
3595	3615	Granite wash
	3615	Rotary Total Depth

Drilled 275' 12 1/4" hole. Ran 7 joints of 8-5/8" surface casing. Set at 272.47'. Cemented with 190 sacks of 60/40 posmix, 3% CaCl, 2% gel. Job was complete at 3:30 a.m., February 17, 1978.

T.D. 3615'. Ran 91 joints of 4 1/2" - 9 1/2# casing. Set at 3613'. Cemented with 150 sacks cement, 25 sacks 50/50 posmix, 12 1/2# gilsonite per sack, 125 sacks 50/50 posmix, 2% gel, salt saturated, 3/4 of 1% CFR friction reducer. Job complete at 2:45 p.m., February 26, 1978.

SAMPLE TOPS:

Anhydrite	1972
B/Anhydrite	1999

RECEIVED
STATE CORPORATION COMMISSION

MAR 08 1978

REGISTRATION DIVISION
STATE CORPORATION COMMISSION

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Atherton #2, C SW SW Section 5-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By *Jack L. Partridge*
Jack L. Partridge, Ass't. Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 6th day of March, 1978.

My commission expires July 21, 1979.

Sandra Richman
Sandra Richman, Notary Public

