

29-1-26W
off SW SW SE

CONTRACTOR'S WELL LOG

P-144 BOPD N/W AKC

OPERATOR:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc. ER 37
WELL NAME:	<u>CHAMBERS #1</u>
LOCATION:	<u>Approx. SW SW SE, Sec. 29-1S-26W</u> Decatur County, Kansas
GEOLOGIST:	Jack K. Wharton
SPUD DATE:	June 12, 1971
COMPLETION DATE:	June 19, 1971

0	112	Clay
112	118	Flint & Pyrite
118	240	Shale & Lime
240	1015	Shale
1015	1123	Sand
1123	1967	Shale
1967	1996	Anhydrite
1996	2180	Shale
2180	3309	Shale & Lime
3309	3352	Lime & Shale
3352	3490	Lime
3490	3598	Lime & Shale
3598	3610	Lime
	3610	Rotary Total Depth

Drilled 268' of 12-3/4" surface hole, set 7-5/8" surface csg. at 256' w/200 sx. Sunset cement. Plug was down at 1:00 a.m. 6-12-71. Ran 4 1/2" csg. set at 3606' w/50 sx. posmix, 2% gel, and 12 lbs. gilsonite per sack. Followed w/75 sx. common cement, 2% gel, 10% salt, 1% c.c. and 3 lbs. friction reducer, D.V. Tool at 1986'. Cemented w/250 sx. 50/50 posmix, 6% gel. Cement circulated. Job completed at 3:15 p.m. 6-19-71.

<u>ELECTRIC LOG TOPS</u>	
Anhydrite	1969 (+ 551)
B/Anhydrite	1996 (+ 524)
Heebner	3256 (- 736)
Toronto	3292 (- 772)
Lansing	3301 (- 781)
B/K.C.	3500 (- 980)
Granite Wash	3601 (-1081)
ELTD	3611 (-1091)

<u>ELEVATION:</u>
2520 K.B.
2518 D.F.
2512 G.L.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the CHAMBERS #1, Approx. SW SW SE, Sec. 29-1S-26W, Decatur County, Kansas.