


(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)

4-1-26W

API-15-039-20,230



Lease Name: Sumner "C" Well No. 2
Well Located: Approx. C NW SE
Decatur County SEC 4 TWP 1S RGE 26W
Operator: A. L. Abercrombie, Inc.
Address: 801 Union Center
Elevation: Ground 2506 D.F. 2512 K.B. 2514
Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: March 21, 1972 Drilling Completed: March 28, 1972
Well Completed: 19 Total Depth 3605'
Initial Production: D & A

Casing Record

Size: 8-5/8" Set at 214' Size: Set at
Size: Set at Size: Set at

Liner Record


Size: Set from To

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8-5/8"</u>	<u>150</u>	<u>Common</u>
<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>

Perforations

Formation	Perforated Interval and Number Shots
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>



Electric Log Run (Show type log and depths covered)

None

(Fill in formation and related information on reverse side)

FORMATION, TESTING AND COMPLETION RECORD

4-1-26W

p. 2

Show Drill Stem Tests,
Well Stimulation and
Production Tests

Formation	Top	Bottom	
Toronto & Lansing	3259	3311	DST #1 - Open 30" - 30" - 30" - 45" Recovered 30' heavy mud IFP 31-31#, FFP 53-53#, IBHP 784#, FBHP 784#. BHT 93°.
Lansing	3323	3350	DST #2 - 15" - 30" - 30" - 45" Recovered 5' mud IFP 21-21#, IBHP 32#, FFP 21-21#, FBHP 38#. BHT 93°.
Lansing	3423	3485	DST #3 - 30" - 30" - 30" - 30" Recovered 120 feet heavy mud and 265 feet watery mud. IFP 234-234#, IBHP 277#, FFP 234-234#, FBHP 266#. BHT 95°.

SMP TOPS	DEPTH			
ANHY	1979	0	105	Clay and Sand
B ANHY	2009	105	131	Flint
HEEB	3251	131	1025	Shale
TOR	3285	1025	1145	Sand
LANS	3290	1145	1383	Shale w/Sand Streaks
BKC	3502	1383	1485	Sand
GR WASH	3588	1485	1677	Shale
RTD	3605	1677	1730	Bentonite
		1730	1979	Shale & Shells
		1979	2009	Anhydrite
		2009	2180	Shale
		2180	2570	Shale & Lime
		2570	3225	Lime & Shale
		3225	3525	Lime
		3525	3585	Shale & Lime
		3585	3605	Shale & Granite Wash
			3605	Rotary Total Depth

Drilled 216' of 12½" surface hole. Set 8-5/8" surface csg. at 206' w/110 sx. on bottom and 40 sx. on top. Cement circulated. Plug was down at 6:30 a.m. 3-22-72. Dry and Abandoned

SAMPLE TOPS	
Anhydrite	1979 (+ 535)
B/Anhydrite	2009 (+ 505)
Heebner	3251 (- 737)
Toronto	3285 (- 771)
Lansing	3290 (- 776)
B/K.C.	3502 (- 988)
Granite Wash	3588 (-1074)

ELEVATION
2514 K.B.
2512 D.F.
2506 G.L.

