

CONTRACTOR'S WELL LOG

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

Tracey Enterprises, Inc.
Abercrombie Drilling, Inc.
Atherton #1
C SE SW Section 5-1S-26W
Decatur County, Kansas
January 29, 1978
February 4, 1978

0	41	Clay & sand
41	300	Sand & shale
300	1945	Shale
1945	1975	Anhydrite
1975	2586	Shale
2586	2734	Shale & lime
2734	2866	Shale
2866	3207	Lime & shale
3207	3270	Shale & lime
3270	3355	Lime
3355	3443	Shale
3443	3542	Lime & shale
3542	3565	Lime
	3565	Rotary Total Depth

Spud hole at 1:30 p.m., January 29, 1978. Drilled 300' of 12 $\frac{1}{4}$ " hole. Ran 7 joints of 8-5/8" - 28# surface casing. Set at 298'. Cemented with 210 sacks 60/40 posmix, 2% gel, 3% CaCl. Plug was down at 8:30 p.m., January 29, 1978.

T. D. 3565'. Ran 88 joints of 4 $\frac{1}{2}$ " - 10 $\frac{1}{2}$ # casing. Set at 3558' K.B. Cemented with 125 sacks cement, first 25 sacks of 50/50 posmix, 2% gel, 12 $\frac{1}{2}$ # gilsonite per sack, followed with 100 sacks of common cement, salt saturated, 3/4 of 1% CFR-2. Job complete at 6:45 p.m., February 4, 1978.

SAMPLE TOPS:

Anhydrite	1946' (+535)
B/Anhydrite	1975' (+506)

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Atherton #1, C SE SW Section 5-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge, Ass't. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state, as of this 8th day of February, 1978.

NOTARY

My commission expires July 21, 1979.

Sandra Richman
Sandra Richman, Notary Public