

WICHITA COUNTY

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

Tracey Enterprises, Inc.
Abercrombie Drilling, Inc.
Atherton #3
1320' FWL & 495' FSL
Section 5-1S-26W
Decatur County, Kansas
March 7, 1978
March 19, 1978

SPUD DATE:
COMPLETION DATE:

0	134	Clay & sand
134	170	Sand & shale
170	258	Shale
258	1945	Sand & shale
1945	1960	Anhydrite
1960	2410	Shale
2410	2656	Sand & shale
2656	2886	Shale
2886	3246	Shale & lime
3246	3250	Lime & shale
3250	3300	Lime
3300	3435	Lime & shale
3435	3542	Lime
	3542	Rotary Total Depth

Spud hole at 9:45 p.m., March 7, 1978. Drilled 258' of 12 1/4" hole. Ran 6 joints of 8-5/8" surface casing. Set at 257' K.B. with 200 sacks of cement, 60/40 posmix, 2% gel, 3% CaCl. Plug was down at 2:45 a.m., March 8, 1978.

T.D. 3542'. Ran 89 joints of 4 1/2", 9.5# casing. Set at 3538' K.B. with 125 sacks 50/50 posmix, 2% gel, 3/4 of 1% CFR-2, salt saturated, and 25 sacks of 50/50 posmix, 2% gel, 12 1/2# gilsonite per sack. Job was complete at 6:15 p.m., March 19, 1978.

SAMPLE TOPS:

Anhydrite 1934'
B/Anhydrite 1960'

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Atherton #3, 1320' FWL & 495' FSL Section 5-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge
Jack L. Partridge, Ass't. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 23rd day of March, 1978.

My commission expires July 21, 1979.

Sandra Richman
Sandra Richman, Notary Public

