

## CONTRACTOR'S WELL LOG

5-1-26W

OPERATOR:  
 CONTRACTOR:  
 WELL NAME:  
 LOCATION: *State Survey*  
*WICHITA BRANCH*

SPUD DATE:  
 COMPLETION DATE:

Tracey Enterprises, Inc.  
 Abercrombie Drilling, Inc.  
 Atherton #6  
 330' FWL, 330' FSL  
 Section 5-1S-26W  
 Decatur County, Kansas  
 April 21, 1978  
 April 22, 1978

0	135	Clay, rock & sand
135	1454	Shale
1454	1670	Shale & sand
1670	1724	Sand
1724	1946	Shale
1946	1960	Anhydrite
	1960	Rotary Total Depth

Spud at 10:30 a.m., April 21, 1978. Drilled 300' of 12 $\frac{1}{4}$ " hole. Ran 7 joints of 8-5/8" - 28# casing. Set at 299' with 180 sacks of 60/40 posmix, 2% gel. Cement did circulate. Plug was down at 4:30 p.m., April 21, 1978.

T.D. 1960'. Completed as salt water disposal well. Ran 49 joints of 5 $\frac{1}{4}$ " - 14# S.T.&C. J-55 steel casing. Set at 1959'. Cemented with 450 sacks of 50/50 posmix, 2% gel. Cement did circulate. Job complete at 11:15 p.m., April 22, 1978.

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Atherton #6, 330' FWL & 330' FSL Section 5-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge,  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me a Notary Public, in and for the aforesaid county and state as of this 25th day of April, 1978.

Sandra Richman