



7-1-26W

April 12, 1978

KANSAS GEOLOGICAL SURVEY
Wichita Well Sample Library
4150 Monroe Street
Wichita, Kansas 67209

RE: "Kansas Drillers Log"

Gentlemen:

Enclosed for your use, please find the required number (1) of the above referenced form for the following well and location:

#1-7 Martin, 550' FNL & 440' FEL, Section 7, T1S, R26W, Decatur County,
Kansas.

Thank you.

Cordially

EXETER EXPLORATION COMPANY


Jean E. Enstrom


/jee
Enclosure

cc: WI Partners,
w/enc.

State Geological Survey
KANSAS DRILLERS LOG
WICHITA BRANCH
API No. 15 — 039 — 20,413
County Number

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-039-20413
7-1-26w
S. 7 T. 1 R. 26 E
Loc. 550' FNL & 440' FEL
County Decatur



Elev.: Gr. 2508
DF 2512' KB 2513'

Operator
Exeter Exploration Co.

Address
2300 Lincoln Center Bldg. Denver, Colo 80264

Well No. #1-7 Lease Name Martin

Footage Location
550' feet from ~~XXX~~ (S) line 440' feet from (E) ~~XXX~~ line

Principal Contractor Murfin Drilling Company Geologist Jim Price

Spud Date 4-3-78 Total Depth 3639' P.B.T.D. N.A.

Date Completed 4-11-78 Oil Purchaser None

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Casing	12-1/4"	8-5/8"	-	239'		200	

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
-	-	-

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
None		

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
TREATMENT: None	

PLUGGING DETAIL: Well plugged with 160 sxs 50-50 posmix cement with 6% gel as follows:
3639' : 30 sxs 1100' : 70 sxs 40' : solid plug with
3350' : 30 sxs 200' : 20 sxs 10 sxs.

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
N.A.	N.A.				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	N.A. bbls.	N.A. MCF	N.A. bbls.	N.A.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
N.A.			N.A.		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Exeter Exploration Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:		
Well No. 1-7	Lease Name Martin		Dry Hole	
S <u>7</u> T <u>1S</u> R <u>26</u> ^{EX} _W				
WELL LOG			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 : Lansing Kansas City 30"-60"-60"-120" Rcc 20' SOCM, 100' wtry mud 630' MC Wtr FP 42-222, 234-378 SIP 982-925 HP 1730-1714	3248	3308	Stone Corral Lansing KC Base Lansing KC Reagan Granite TD	1981 3284 3494 3592 3602 3639
DST #2 : Lansing Kansas City 30"-60"-30"-90" Rec 15' oil specked mud FP 33-41, 41-41 SIP 66-58 HP 1836-1811	3452	3480	Log: IES Sonic	
DST #3 : Reagan 30"-60"-60"-120" Rec 120' GIP, 120' clean oil, 60' OCM, 60' SOCM, 1335' Salt water FP 82-502, 526-730 SIP 901-901 HP 1892-1836	3570	3600		
DST #4 : Reagan 30"-60"-60"-90" Rec. 90' oil, 1310' salt water FP 82-493, 509-705 SIP 925-949 HP 1940-1876	3592	3639		
DST #5 : Reagan (Straddle) 30"-60"-60"-120" Rec. 297', mud with NS FP 164-181, 189-197 SIP 460-477 HP 1957-1876	3584	3597		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
Date Received	 Signature District Geologist Title 4-11-78 Date			