

OCT 10 1970

CONTRACTOR'S WELL LOG

C NE NE
8-1-26W

Elev. 2501' KB

OWNER:
CONTRACTOR:
WELL NAME:
LOCATION:

GEOLOGIST:
SPUD DATE:
COMPLETION DATE:

Abercrombie Drilling, Inc.
Abercrombie Drilling, Inc.
BLEES #1
C NE NE, Sec. 8-1S-26W
Decatur County, Kansas
Jack Wharton
January 22, 1969
January 31, 1969

PMP 164 BOPD, NW
J K C

0	98	Clay
98	113	Pyrite
113	235	Sand & Shale
235	1000	Shale & Shells
1000	1200	Sand
1200	1654	Shale
1654	1743	Sand
1743	1965	Shale
1965	1982	Anhydrite
1982	2465	Shale
2465	2665	Shale w/Lime Streaks
2665	3280	Lime & Shale
3280	3599	Lime
	3599	Rotary Total Depth

Drilled 230' of 9" surface hole and set 221' of 7" casing w/125 sx. Sunset cement.
Plug was down 10:30 p.m., 1-22-69.
Set 4 1/2" csg. @3598 w/150 sx. DV Tool was set @1980' w/260 sx.

ELECTRIC LOG TOPS

ELEVATION

Heebner	3228	(- 727)	2501 K. B.
Toronto	3266	(- 765)	2499 D. F.
Lansing	3273	(- 772)	2493 G. L.
Base/K.C.	3479	(- 978)	
Sand	3546	(-1045)	
Reagan Sand	3567	(-1066)	
Gran. Wash	3572	(-1071)	
E.L.T.D.	3598	(-1097)	

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack K. Wharton, Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BLEES #1, C NE NE, Sec. 8-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jack K. Wharton
Jack K. Wharton