

~~AUG 16 1969~~

OCT 25 1969

CONTRACTOR'S WELL LOG

8-1S-26W


OPERATOR
WELL NAME
LOCATION

A. L. Abercrombie, Inc.
BLEES #2
140' SE of NW NE, 8-1S-26W
Decatur County, Kansas
Jack K. Wharton
June 16, 1969
June 24, 1969

GEOLOGIST
SPUD DATE
COMPLETION DATE

0	55	Clay
55	95	Sand
95	1662	Shale
1662	1740	Sand
1740	1955	Shale
1955	1983	Anhydrite
1983	2235	Shale
2235	2486	Shale w/Shells
2486	2680	Shale & Lime
2680	3115	Lime & Shale
3115	3466	Lime
3466	3565	Lime & Shale
3565	3571	Sand
	3571	Rotary Total Depth

oil



Drilled 254' of 12-1/4" surface hole and set 8-5/8", 24# csg. @244' w/200 sx.
Sunset cement. Cement circulated. Plug was down at 4:00 p.m., 6-16-69.
Ran 5-1/2", 15# csg. and set @3482' w/150 sx. cement. Plug was down at 9:00 p.m., 6-24-69.

FORMATION SAMPLE TOPS

ELEVATION

Top/Anhydrite	1955	(+ 539)	2494 K.B.
Heebner	3221	(- 727)	2492 D.F.
Toronto	3256	(- 762)	2486 G.L.
Lansing	3261	(- 767)	
Base/K. C.	3474	(- 980)	
Reagan Sand	3560	(-1066)	
Base/Reagan Sd.	3565	(-1071)	

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

A. L. Abercrombie, President of A. L. Abercrombie, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Bles #2, 140' SE of NW NE, Section 8-1S-26W, Decatur County, Kansas.

A. L. Abercrombie

Worn to before me, a Notary Public, in and for the State of Kansas, County of Sedgwick,
of this 30th day of June, 1969.