

NOV 20 1969

CONTRACTOR'S WELL LOG

OWNER:	A. L. Abercrombie, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
LEASE:	HUFF "B" #3
LOCATION:	140' N/ C NE SE; Sec. 8-18-26W Decatur County, Kansas
SPUD DATE:	August 31, 1969
COMPLETION DATE:	September 8, 1969
GEOLOGIST:	Jack K. Wharton

oil

0	90	Clay, Pyrite and Sand
90	880	Shale
880	1070	Sand
1070	1275	Shale & Shells
1275	1606	Shale & Gyp
1606	1705	Sand
1705	1929	Shale
1929	1959	Anhydrite
1959	2110	Shale
2110	2440	Shale & Shells
2440	2785	Shale & Lime
2785	3190	Lime & Shale
3190	3500	Lime
3500	3560	Lime & Shale
	3560	Rotary Total Depth



Drilled 234' of 11" surface hole and set 7-5/8" csg. @ 223' w/125 ax. Sunset cement. Cement circulated. Plug was down at 9:00 P.M., 8-31-69.
 Ran 4 1/2" csg. and set at 3453'. Job completed at 1:00 A.M., 9-8-69.

FORMATION	SAMPLE TOPS	ELEVATION
T/Anhydrite	1930 (+530)	2460 K.B.
B/Anhydrite	1959 (+501)	2458 D.F.
Heebner	3197 (-737)	2452 G.L.
Toronto	3232 (-772)	
Lansing	3239 (-779)	

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

A. L. Abercrombie, President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the Huff "B" #3, 140' N/ C NE SE, Sec. 8-18-26W, Decatur County, Kansas, as of this 8th day of September, 1969.

ABERCROMBIE DRILLING, INC.

A. L. Abercrombie

A. L. Abercrombie