

9-1-26W
9-1-26W
CSW NW

JAN 3 1970

CONTRACTOR'S WELL LOG

OWNER:
CONTRACTOR:
LEASE:
LOCATION:

SPUD DATE:
COMPLETION DATE:
GEOLOGIST:

A. L. Abercrombie, Inc.
Abercrombie Drilling, Inc.
HUFF "A" #2
140' NW C SW NW, Sec. 9-1S-26W
Decatur County, Kansas
September 16, 1969
September 24, 1969
Jack K. Wharton

el 2511 KE
oil

0	106	Clay and Sand
106	125	Pyrite
125	1475	Shale
1475	1648	Shale and Gyp
1648	1754	Sand
1754	1979	Shale
1979	2004	Anhydrite
2004	2711	Shale
2711	2875	Shale and Lime
2875	3297	Lime and Shale
3297	3540	Lime
	3540	Rotary Total Depth

Drilled 240' of 12½" surface hole and set 8 5/8", 20# csg., w/275 sx cement at 234'. Plug down. 1:30 P.M. 9-17-69. Cement circulated.
Set 4½" Csg. @ 3539'. Cemented w/50 sx. 50-50 posmix cement w/2% gel and 600# gilsonite. Set DV tool @ 1990'. Cemented w/250 sx. 50-50 posmix w/4% gel.

FORMATION SAMPLE TOPS		ELEVATION
Top Anhydrite	1979 (+532)	2511 K.B.
Base Anhydrite	2004 (+507)	2509 D.F.
Heebner	3243 (-732)	2503 G.L.
Toronto	3279 (-768)	
Lansing	3285 (-774)	
Base Kansas City	3495 (-984)	
Total Depth	3540	

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

A. L. Abercrombie, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Huff "A" #2, 140' NW C SW NW, Section 9-1S-26W, Decatur County, Kansas, as of this 25th day of September, 1969.

ABERCROMBIE DRILLING, INC.
A. L. Abercrombie