

CONTRACTOR'S WELL LOG

OPERATOR: Sauvage Drilling Company, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: HUFF "C" #1
 LOCATION: SW NE, Section 9-1S-26W
 Decatur County, Kansas
 SPUD DATE: 4/04/81
 COMPLETION DATE: 4/09/81

0	1634	Sand & Shale
1634	1732	Sand
1732	1958	Shale
1958	1985	Anhydrite
1985	2693	Shale
2693	3330	Lime & Shale
3330	3470	Lime
3470	3586	Lime & Shale
	3586	Rotary Total Depth

Spud hole @ 2:00 p.m., 4/04/81. Cut 250' of a 12 1/4" hole. Came out of the hole. Went in with Bit #1 7-7/8" DTJ. Came out of the hole. Ran 6 jts. of 8 5/8" - 23# casing (tally 241.55) Set @ 249' with 250 sacks of 60-40 posmix, 3% c.c., 2% gel. Plug was down @ 12:00 noon, 4/05/81. Cement did circulate. 7:00 a.m. drilling @ 2256'.

T.D. @ 3586'. Ran 89 joints of 4 1/2" - 9 1/2# casing (tally 3580') Set @ 3586'. Ran 10 bbls. of Chemical Flush with 300 sacks of Halliburton Lite, followed with 200 sacks of 60-40 posmix. Plug was down @ 1:00 p.m., 4/09/81.

● SAMPLE TOPS:
 Anhydrite 1955'
 B/Anhydrite 1985'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the HUFF "C" #1, Section 9-1S-26W, Decatur County, Kansas.

RECEIVED
 CONSERVATION COMMISSION
 APR 22 1981
 CONSERVATION DIVISION
 Wichita, Kansas

BY: Jack L. Partridge
 Jack L. Partridge, Vice P.