

10-1-26W

State Geological Survey  
WICHITA BRANCH

CONTRACTOR'S WELL LOG

10-029-25302

OPERATOR:	W. W. Sauvage
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	HUFF #4
LOCATION:	C NE NE Section 10-1S-26W Decatur County, Kansas
SPUD DATE:	April 26, 1976
COMPLETION DATE:	May 5, 1976

0	129	Shell & Sand
129	139	Flint
139	223	Shale & Sand
223	1175	Shale
1175	1230	Sand
1230	1616	Shale
1616	1750	Sand
1750	1980	Shale
1980	2009	Anhydrite
2009	2545	Shale
2545	2649	Shale & Lime
2649	2740	Lime & Shale
2740	2858	Shale
2858	3319	Shale & Lime
3319	3590	Lime
	3590	Rotary Total Depth

Drilled 223' of 12 1/4" hole. Ran 5 jts. 8 5/8" casing, 28#. Set @ 223' K.B. Cemented with 160 sx. 60/40 Posmix, 2% gel, 3% ca. cl. Cement did circulate. Plug was down @ 10:45 p.m. April 26, 1976.

97 joints of 4 1/2", 9 1/2# casing, Set @3440' K.B. w/50 sx. of Halliburton lite & 100 sx. of 50/50 Posmix. Plug was down @ 5:15 p.m. May 5, 1976.

SAMPLE TOPS:

Anhydrite	1980' (+531)
B/Anhydrite	2009' (+502)

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the HUFF #4, C NE NE, Section 10-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, Inc.

By: *Jerry A. Langrehr*  
 Jerry A. Langrehr, Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 10th day of May, 1976.

*Diane Steincamp*  
 Diane Steincamp - Notary Public

Commission Expires: February 18, 1980.

