

DEC 30 1972

CONTRACTOR'S LOG

OPERATOR: W. W. Sauvage Inc.
CONTRACTOR: Abercrombie Drilling Inc.
WELL NAME: HUFF #1-A
LOCATION: 100' SE of C NW NE
Sec. 10-1S-26W Decatur Co., Ks.
GEOLOGIST: Jack K. Wharton
SPUD DATE: September 23, 1972
COMPLETION DATE: September 29, 1972
35 H2O LK

0	118	Clay
118	131	Flint
131	285	Shale
285	1248	Sand & Shale
1248	1300	Sand
1300	1595	Shale
1595	1747	Sand
1747	1970	Shale
1970	1999	Anhydrite
1999	2085	Shale
2085	2415	Shale, Sand & Bostonite
2415	2665	Shale
2665	3295	Lime & Shale
3295	3525	Lime
	3525	Rotary Total Depth

1. 139' ± 12" surface hole. Set 8-5/8" surface casing at 234' A.B. 50 sy.
Cement circulated. Plug was down at 4:00 p.m. 9-23-72. 2a 1/2" s t
± 35' w/2 1/2 sx. cement. Job completed 9-29-72.

SAMPLE TOPS		ELEVATION
Anhydrite	1970 (+ 527)	2497 K.B.
A Anhydrite	1999 (+ 498)	2495 D.F.
Heebner	3245 (- 748)	2489 G.L. Estimated
Toronto	3283 (- 786)	
Lansing	3289 (- 792)	
B K.C.	3500 (-1004)	
Total Depth	3525 (-1028)	

STATE OF KANSAS)
) SS
COUNTY OF SE WICK)

Lar Ehr, Vice President of Abercrombie Drilling, Inc., do hereby
state above and foregoing is a true and correct copy of the log of the
100' SE of C NW NE, Section 10-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

Jerry A. Ehr
Vice President