

CONTRACTOR'S WELL LOG

OPERATOR: W. W. Sauvage
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: HUFF "B" #3
 LOCATION: SW NW, Section 10-1S-26W
 Decatur County, Kansas
 SPUD DATE: 06-25-80
 COMPLETION DATE: 07-05-80

0	95	Sand, Clay & Rock
95	200	Blue Shale
200	1350	Shale
1350	1575	Shale & Sand
1575	1732	Sand & Shale
1732	1896	Shale
2088	2492	Shale & Sand
2492	2635	Shale
2635	2844	Shale & Lime
2844	3153	Lime & Shale
3153	3270	Shale & Lime
3270	3535	Lime & Shale
	3535	Rotary Total Depth

Spud rathole at 5:15 p.m., 06-25-80. Flint rock. Spud surface hole at 11:15 p.m. 7:00 a.m., 06-26-80 drilling a 17-1/4" hole at 92'. Ran 5 joints of 13-2/3" casing 48# (tally 200.57) Set at 200'. Cemented with 170 sacks of 60/40 posmix cement, 3% c.c., 2% gel. Cement did circulate. Cement by Sun Cement. Plug was down at 1:30 p.m. on 06-26-80.

DID 3535', LTD 3537'. Ran 88 joints of 2-1/2" casing, set at 3534'. Cemented with 300 sx. of Halliburton cement.

SAMPLE TOPS:

Anhydrite 1896'
 B/ Anhydrite 1924'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 18 1980
 CONSERVATION DIVISION
 Wichita, Kansas