

K.C. LIBRARY

11-1-26W

KANSAS PreCambrian, the Survey would like to have all the cuttings that contain crystalline samples. This well penetrates the PreCambrian. Samples normally sent to the Wichita Well Sample Library.

IMPORTANT

API No. 15 — 039 — 20,501
 County Number

State Geological Survey
 WICHITA BRANCH

S. 1 T. 1 R. 26 E. W


Operator
Edward J. Ackman

Loc. SW SW

Address
1940 Colorado State Bank Bldg. Denver, Colo 80202

County Decatur
 640 Acres
 N

Well No. #1 Lease Name Cozad



Footage Location
730 feet from (X) (S) line 730 feet from (X) (W) line

Elev.: Gr. 2379

Principal Contractor Stoepelwerth Geologist Roger Welty

Spud Date 5/7/80 Date Completed 5/14/80 Total Depth 3511' P.B.T.D. 3511'

Directional Deviation NONE Oil and/or Gas Purchaser Dry Hole

DF KB 2384

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8				150	2% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Edward J. Ackman		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Cozad	Dry Hole
S 11 T 1 R 26 E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST No. 1 (LKC "A") 3142-3200 30-30 - 30-30 Rec. 130' Mud w/few oil spots FP 53-53, 85-95 SIP 735-702 HP 1628-1597, BHT 102°			Stone Corral	1851
			B. Stone Corral	1877
			Heebner	3139
			Lansing-KC	3176
			LKC "B"	3221
			LKC "C"	3258
			LKC "D"	3289
DST No. 2 (LKC "B" & "C") 3194-3280 Misrun			LKC "E"	3332
			LKC "F"	3354
			Base LKC	3387
			Reagan	3464
DST No. 3 (LKC "B" & "C") 45-30 - 45-30 60' OCMW (24% oil, 69% mud, 7% wtr.) 120' OCMW (12% oil, 30% wtr., 58% M) FP 95-117, 138-159 SIP 788-745 HP 1649-1628, BHT 103°				
DST No. 4 (LKC "E" & "F") 3306-3385 30-30 - 30-30 Rec. 8' Mud FP 31-31, 42-42 SIP 1681-1649, BHT 104°				
DST No. 5 (Reagan Sand) 3433-3474 30-30 - 30-30 Rec. 10' SOCM (2% oil, 98% Mud) FP 31-31, 42-42 SIP 319-223 HP 1765-1744, BHT 104°				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	Exploration Manager
	Title
	July 18, 1980
	Date