

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


18-1-26w

Company- MURFIN DRILLING CO., BUD AINSWORTH
Farm- J. Bremer No. 1

SEC. 18 T. 1 R. 26W
NW NW NW

Total Depth. 3602' RTD.
Comm. 4-16-1962 Comp. 4-22-1962
Shot or Treated. No
Contractor. Murfin Drilling Company
Issued. 8-4-1962

County Decatur
KANSAS



CASING:

8 5/8" 203' W/175 sks. Cem.,

Elevation. 2500' KB.

Production. DRY. (PRE GAMB)
ABD.

Figures Indicate Bottom of Formations.

Shale	1055
Sand-Shale	1668
Shale	1700
Red Bed & Shale	1969
Anhydrite	1993
Shale & shells	2600
Shale & Lime	2770
Lime & shale	2920
Shale & Lime	3075
Lime & Shale	3240
Lime	3580
Lime & Granite	3602 RTD.
TOTAL DEPTH	3602

ELECTRIC LOG TOPS:

Anhydrite	1971
Topeka	3119
Lansing / Kansas	
City	3267
Base / Kansas City	3480
Precambrian	3594
Total Depth	3602

DRILL STEM TEST:

No. 1 3280'-3360' Open 1
hr. Weak blow 23 min.
Recovered 50'
mud with a few specks of
oil. IF 15# FF 31# FBHP
723# / 20 Min.,