

JAN 16 1971

16-1-26W
150's 9 C SW E

P 66BOPD + 44BWP
LKC

WELL LOG

Company:

Donald C. Slawson
Suite 408 One Twenty Building
Wichita, Kansas 67202

Lease:

Huff 'B' #2
150' South of C SW SW, Section 16-1-26W
Decatur County, Kansas

Total Depth:

3415' Elevation: 2421 K.B.

Contractor:

Slawson Drilling Company, Inc.

Commenced:

April 6, 1970

Completed:

April 11, 1970

Casing:

8 5/8" at 257' with 225 sx cement
4 1/2" at 3414' with 125 sx cement

0-257	Surface Clay & Sand
257-300	Shale
300-1874	Shale & Shells
1874-1904	Anhydrite
1904-2892	Shale & Lime
2892-3205	Lime & Shale
3205-3415	Lime
3415	Total Depth

Sample Log

Anhydrite	1877
B. O.	1904
Heebner	3159
Jaronto	3191
LKC	3197
BKC	3404

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Maxine V. Starr, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Huff 'B' #2 well.

Maxine V. Starr
MAXINE V. STARR

